

Chartered Professional Engineers and Scientists

# Traffic Management Plan Falls Festival 2020/21 at North Byron Parklands, Yelgun, NSW

Author: Hayden Kress Date: 23/06/2020

Chartered Professional Engineers and Scientists

### **Contact Information**

43 Main Street Clunes NSW 2480

Telephone: 02 6629 1552

office@aldersonassociates.com.au www.aldersonassociates.com.au

#### **Document Information**

Document title

Traffic Management Plan for Falls Festival 2020/21 at North

Byron Parklands, Yelgun, NSW

Reference

20470 TMP Rev1

Job number 20470

Revision Rev 0 22/06/2020 summary Rev 1 23/06/2020

### Personnel

Hayden Kress, BEng(Civil) Hons RMS Prepare a Work Zone TMP (SOC 213014)

Chartered Professional Engineers and Scientists

## **Table of Contents**

1.0	Introduction	4
1.1	Project brief	4
1.2	Relevant standards, specifications and guidelines	4
Defi	nitions	5
1.3	Site location	6
1.4	Event description	7
1.5	Event Calendar	8
1.6	Conditions of Consent	8
1.	.6.1 D16 – Table 6, Traffic Management	8
1.	.6.2 D27 – Traffic Management Plan	9
1.	.6.3 D29 – Traffic Control Plan	9
2.0	Large Event	10
2.1	Observations from Previous Falls Festivals at the site	10
2.2	Traffic Management Approach for the Falls Festival 2020/21	11
2.3	Temporary Bus Bay Brunswick Heads	12
2.4	Stacked parking and camping	12
3.0	Traffic impact modelling	15
4.0	Contingencies and emergency evacuation	15
5.0	Monitoring for Traffic Management During the Festival	16
6.0	Risk assessment	17
7.0	Copies of the Traffic Management Plan	20
8.0	Audit checklist	20
9.0	Responsible organisations contact persons and signatures	22
10.0	Approval condition compliance summary table	23
11.0	Chain of command	23
12.0	Conclusions and recommendations	24
V DDEV	NDIY A Traffic control plans	25

Chartered Professional Engineers and Scientists

#### 1.0 Introduction

Greg Alderson and Associates (GAA) have been engaged by *Look up and Live Pty Ltd* to update the Traffic Management Plan from previous events for the Falls Festival Byron at North Byron Parklands in Yelgun that is to be held during the New Year's period of 2020/21. The festival will be held from 31 December 2020 to 2 January 2021. Camper bump in will commence on Tuesday 29 December 2020, allowing an additional day for arrivals of camping patrons compared to events prior to 2018/19. The camping areas close in the afternoon of 3 January 2021.

Following on from the Traffic Evaluation Report observations and recommendations for previous Falls Festival events, together with updated approvals provided under State Significant Development 8169 Development Consent, it is proposed to implement the following traffic improvements for the 2020/21 event:

- Gates will be open from 29 December (subject to ticket sales exceeding 20,000) to allow an additional day for camping patrons to arrive before the event commences;
- Contingency TCP is included for managing potential queueing incident that may have the potential to impact the Pacific Motorway;
- Egress route for Northbound traffic via new Gate E to Wooyung Rd, together with associated TCPs.

It is proposed that this years event will have a patronage of up to 35,000 which is classed as the Large Summer Event.

#### 1.1 Project brief

The aim of the Traffic Management Plan (TMP) is to prescribe traffic management and control procedures for the Falls Festival at Yelgun, in order to satisfy the conditions of consent as set out in the Development Approval from the Independent Planning Commission, dated 13<sup>th</sup> March 2019 and in accordance with recent modifications to the consent. In conjunction with this Traffic Management Plan a Traffic Monitoring Protocol will be developed by our office. These documents will set out data collection methods in order to provide sufficient data to assess future and potentially larger events at the event site.

#### 1.2 Relevant standards, specifications and guidelines

This TMP has been prepared in accordance with the following standards, specifications and guidelines:

- RMS Guide to Traffic and Transport Management for Special Events Version 3.5
- RMS Traffic Control at Worksites manual
- Australian Standards (in particular AS1742)
- Quality Assurance specifications
- Austroads Guide to Traffic Management

Chartered Professional Engineers and Scientists

#### **Definitions**

AADT Average Annual Daily Traffic; average traffic volume per day after application

of correction factors.

ADT Average Daily Traffic; average traffic volume per day, based on a limited

survey period, typically 1 week.

Background Traffic Traffic composition as would typically exist without superposition of event

traffic.

BVW Brunswick Valley Way.
FFB Falls Festival Byron.

**Heavy Vehicle** For the purposes of this report; anything other than a pedestrian, cyclist,

motorbike or car.

**KPI** Key Performance Indicator; as defined in the conditions of consent for the

development.

Los Level of Service; Service level of roads based on certain traffic statistics as

defined in other documents.

**NBP** North Byron Parklands.

**Peak Flow Rate** Hourly volume of vehicles during busiest part of assessment period.

**PER** Performance Evaluation Report.

TCP Traffic Control Plan.

TMP Traffic Management Plan.

TSC Tweed Shire Council.

TVW Tweed Valley Way.

#### 1.3 Site location

The subject site is formally known as Lots 46, 402-404, 410 DP 755687; Lots 10, 12, 14 DP 875112; Lots 2, 12 DP 848618; Lot 101 DP 856767; Lots 30-31 DP 880376; Lots 101-102, 107 DP 1001878; Lot 1 DP 1145020, Tweed Valley Way and Jones Road, Yelgun. The southernmost entry to the site is located at approximately 1km to the North from the Yelgun Interchange and Yelgun Rest Area.

Figure 1 below depicts the location of the site with respect to its locality.




Figure 1 - Site locality, Source of map: Google Maps 2015

Chartered Professional Engineers and Scientists

#### 1.4 Event description

The Falls Festival Byron is a music and arts festival that will be held at North Byron Parklands from 31 December 2020 until 2 January 2021.

Falls Festival operates in such a way that it is held at other locations in the same period, so that artists can be transported between event locations. In that format it has been held successfully at Marion Bay in Tasmania and Lorne in Victoria for over 25 years.

The Falls Festival was held at North Byron Parklands for the first time during the 2013/14 New Year's Eve period and held each year since that date. All festivals were a success from a traffic engineering perspective with no major impacts on the public roads during peak arrival periods.

Although the event days are 31 December 2020 until 2 January 2021, the campgrounds will open on 29 December 2020 (subject to ticket sales) and close on 3 January 2021, allowing camping patrons to arrive a day earlier if they choose to purchase the appropriate ticket. We expect this to be a very effective measure to reduce the likelihood of any significant queuing incidents on Tweed Valley Way.

It will only be necessary to implement this measure if patron numbers are to exceed 20,000. Smaller events are unlikely to have peak arrival periods causing queueing external to the site and therefore will not require an additional arrival day. Three types of tickets, plus a camping ticket will be sold for this event and are summarised in Table 1.

As compared to previous years, separate tickets will be required to be purchased to camp on the site. This TMP has been based on the assumption the number of campers and flow rates remains similar to previous years. Festival Management will monitor sales of camping tickets to confirm this assumption remains true. If not, contingency plans should be put in place.

With the additional day being available for camping patron arrivals early on 29 December, it is anticipated that peak arrival rates for camping vehicles will not likely cause any KPI breaches. The estimated arrival profile is:

- Sunday 29 December 20% of camping patrons
- Monday 30 December 60% of camping patrons
- Tuesday/ Wednesday/Thursday 20% of camping patrons
- Friday 3 January Egress

Table 1 - Overview of ticket types

Ticket name	Arrival dates	Festival entry dates	Departure date	Anticipated number of tickets
3 Day Festival Ticket	29, 30 and 31 Dec	31 Dec – 2 Jan	3 Jan	30,000
2 Day Festival Ticket	31 Dec or 1 Jan	31 Dec – 1 Jan or 1 Jan – 2 Jan	2 or 3 Jan	4,000
1 Day Ticket	31 Dec or 1 Jan or 2 Jan	31 Dec or 1 Jan or 2 Jan	1, 2 or 3 Jan	1,000
Camping Ticket		Applies as additional tick		

Chartered Professional Engineers and Scientists

The Falls Festival will function as an approved 'Large Event' with an anticipated maximum patronage of 35,000 people with additional staff, stallholders, contractors and guests. The fifth column in Table 1 depicts the anticipated number of ticket holders of each ticket type based on information provided to our office by festival management. Validity of this TMP and associated traffic control plans is subject to compliance with these attendance numbers and also providing the additional camping arrival day on 29 December to reduce peak arrivals of camping vehicles.

#### 1.5 Event Calendar

The festival schedule can be summarised as follows:

Tuesday 29/12/19 Camp grounds open day 1 Wednesday 30/12/19 Camp grounds open day 2

Thursday 31/12/19 Event day 1 Friday 1/1/20 Event day 2 Saturday 2/1/20 Event day 3

Sunday 3/1/20 Campground closure, camper departure

Car pass sales are used to control arrival days of patrons. For previous years, typically 60% of car passes are sold for 30 December and the remaining 40% for 31 December. For the 2020/21 event Festival Management will monitor sales of camping tickets to confirm the distribution of camping tickets remains similarly or better distributed across the days for camper arrivals. It is likely that there will be a better distribution with the additional day being made available for camping. Some campers may depart on night of the 2<sup>nd</sup> of January but the majority of campers would leave the site on the 3rd, which is the day that the camping area will close.

#### 1.6 Conditions of Consent

The following is an overview of the consent conditions that have been provided to this office detailing the various conditions that are relevant to the festival traffic operation and are thus relevant to this TMP. This TMP is therefore formally responding to those conditions of consent, as contained within the State Significant Development 8169 Development Consent. A Condition Compliance Summary Table is provided later in this document, summarising what conditions are complied with and in which section of this report they are addressed.

#### 1.6.1 D16 - Table 6, Traffic Management

#### KEY PERFORMANCE INDICATORS

D16. The Applicant must address the KPIs in Table 6 in a PER required under Condition D17. The Planning Secretary may amend the KPIs identified in Table 6 for future events after considering the results of the PER required in Condition D17.

Table 6 Key performance indicators for a large event

Issue	Key Performance Indicators
Traffic Management	<ul> <li>A minimum level of service (LoS) C is to be maintained at the Yelgun interchange including merges and diverges.</li> </ul>
	<ul> <li>The level of service for local traffic and through traffic on the Tweed Valley Way should not fall below a LoS D, with a maximum of LoS E for no more than 4 hours a day.</li> </ul>
	<ul> <li>Queue lengths on the link road between Tweed Valley Way and the Yelgun interchange must be limited to a maximum of 60 metres.</li> </ul>
	<ul> <li>Queue lengths on the interchange ramps must not be within 210 metres of the start of the ramp.</li> </ul>
	<ul> <li>On-site queuing is not to extend onto the Pacific Highway or the Tweed Valley Way a any time.</li> </ul>

Chartered Professional Engineers and Scientists

#### 1.6.2 D27 - Traffic Management Plan

#### TRAFFIC MANAGEMENT

#### Traffic Management Plan

- D27. The Applicant must prepare a Traffic Management Plan for the development to the satisfaction of the Planning Secretary. The Plan must:
  - (a) be prepared by a suitably qualified and experienced person(s);
  - (b) be prepared in consultation with BSC, TSC and RMS;
  - detail the measures to be implemented to ensure road safety and network efficiency, including:
    - ensuring no queuing on Tweed Valley Way and Yelgun Interchange off-ramps;
    - ii. details of traffic diversion strategies;
    - ensuring Gate A is only used by trucks or other heavy vehicles (including buses) on event days and shoulder days associated with large and medium events; and
    - iv. ensuring local traffic movements, including residents of Jones Road and Yelgun Road, are given priority and can access their properties;
  - include demand management strategies to reduce private car use while promoting alternatives forms of transport; and
  - (e) contain a Traffic Monitoring Program to monitor the impact of increased traffic generation on the amenity of the area and the effectiveness of the traffic management measures implemented, including but not limited to:
    - data collection of vehicle arrival and departure times, occupancy rates and directions of travel for staff, campers and day patrons;
    - ii. patronage of bus services, including bus occupancy rates, arrival and departure times
    - modal share by vehicle type, including comparison with the modal share as described in the EIS and RTS.
    - iv. queue monitoring, background travel counts on the Pacific Highway and Tweed Valley Way and vehicle volumes on the Yelgun Interchange; and
    - v. procedures and protocols for monitoring, including frequency.

#### 1.6.3 D29 – Traffic Control Plan

#### Traffic Control Plan

- D29. At least two months prior to any medium or large event, the Applicant must prepare a Traffic Control Plan (TCP) for the development. The Plan must:
  - (a) be prepared by a suitably qualified and RMS accredited Work Site Traffic Controller;
  - (b) be submitted to the Byron and Tweed Local Traffic Committees for endorsement and submitted to BSC and TSC for approval on roads under their control;
  - (c) be designed in accordance with the requirements of the RMS's Manual, Traffic Control at Work Sites Version 2, and the current Australian Standards, Manual of Uniform Traffic Control Devices Part 3, 'Traffic Control Devices for Works on Roads';
  - include details on reduced speed zones and special event clearways and signage to prohibit parking in the surrounding road network and in the Yelgun rest area;
  - include a Traffic Incident Management Plan that details a range of approved contingency measures capable
    of avoiding significant impacts on the level of service. The contingency plan must be fully documented and
    include emergency contact names and phone numbers; and
  - (f) be designed to achieve the traffic key performance indicators under Condition D16.

Following approval of the TCP, a copy of the TCP must be submitted to RMS and the Planning Secretary.

20470 TMP Rev1 9

Chartered Professional Engineers and Scientists

### 2.0 Large Event

The Independent Planning Commission gave development approval for the site on the 13<sup>th</sup> of March 2019 for a variety of events including 'Large' events such as the proposed Falls Festival Byron 2020/21 event.

This is the first year in which Falls festival will be operating under a "Large" event profile. Previous SITG events have been successfully run at this scale or larger at the site. As such, lessons learned from previous SITG events may be directly applicable to the upcoming event.

The event manager can familiarise themselves with previous SITG Traffic Evaluation Reports and TMP's for additional relevant information, noting that SITG is a different type of festival that has significantly higher attendance by day patrons.

#### 2.1 Observations from Previous Falls Festivals at the site

From a traffic engineering perspective, Falls Festival Byron 2018/19 and 2019/20 had many successes, with highlights including reductions in illegal parking at the Yelgun Rest Area and fewer pedestrian movements on the Tweed Valley Way. Two minor failures from the previous 17/18 event in regard to the given Key Performance Indicators (KPI's) were rectified and traffic movements were greatly improved. No KPI breaches were observed during the 19/20 event. As a result, the KPI table from 2019/20 was constructed as below.

Table 2 - KPI Table

		KPI met (Y/N)				
Description	Criterion	Saturday	Sunday	Monday	Tuesday	Wednesday
Maximum queue length	210m from	Υ	Υ	Υ	Υ	Υ
on northbound off ramp	start of diverge		'			
Maximum queue length	210m from	Υ	Υ	Υ	Υ	Υ
on southbound off ramp	start of diverge	I	1	I	1	'
Minimum Level of Service	_	Υ	Υ	Υ	Υ	Υ
on Yelgun Interchange		T	T	I	'	T
Minimum Level of Service	D (E up to 4	γ	Υ	Υ	Υ	Υ
along Tweed Valley Way	hours daily)	T	T	T	T	T
Maximum queue length	60m	Υ	Υ	Υ	Υ	Υ
on Link Road	OUIII	T	T	T	T	ľ
On site queuing not to	0m	Υ	Υ	Υ	Υ	Υ
extend to Pacific Hwy	OIII	I	1	I	1	ľ
On site queuing not to						
extend to Tweed Valley	0m	Υ	Υ	Υ	Υ	Υ
Way						

As recommended previously, contingency traffic control plans will also be required to ensure safe traffic management in the event of KPI breaches.

The adopted Traffic Management Plan SSD 8169 (under the issued consent), recommends bump trucks be available for contingency measures on the Pacific Highway and that mobile VMS vehicles are used for end of queue warning along Tweed Valley Way/ Brunswick Valley Way. These shall be available on standby if required.

Chartered Professional Engineers and Scientists

#### 2.2 Traffic Management Approach for the Falls Festival 2020/21

During previous Falls Festivals, it was observed that during the holiday period, background traffic volumes on Tweed Valley Way and Brunswick Valley Way did not increase significantly. Although traffic volume increases on the Pacific Motorway were monitored, correlation with increases on Tweed Valley Way and Brunswick Valley Way was minimal.

During previous Falls Festivals, traffic controllers were placed on standby to manage any congestion that may occur during arrivals. Generally no issues have been observed, however contingency traffic management was implemented on Tweed Valley Way during the queuing incident on Saturday 30 December 2017, along with internal traffic contingency measures including on site queuing utilising a carpark "snake".

This year the queueing observed in 2017 is likely to be prevented from occurring by opening the site one day early for camping arrivals. If any incident occurs there is a documented contingency TCP that would be implemented. In addition to this, the RMS traffic operations centre stationed at St Helena would be contacted and they may implement electronic warning signage on the permanent signs on the motorway and at Ewingsdale Road to warn motorists approaching the area on the motorway.

Mobile VMS vehicles will be used to warn motorists of end-of queue approaches.

Traffic controllers are implemented at Gate C during the camping departure day with the successfully trialled 2-lane departure. Traffic controllers will be on standby to implement TCP's at Gate E and TVW/ Wooyung Road intersections during camping departure day as required.

At last year's event, the Levels of Service on Tweed Valley Way were satisfactory during departures, and particularly for northbound vehicles there is capacity for a higher departure rate. This will be monitored again this year including during the departures from Gate E.

This year, traffic controllers are proposed to be used on the public roads as required:

- at Gate C during the 2-lane camping departure;
- at Jones Road for managing heavy vehicle arrivals;
- at Gate E to manage camping departures;
- at the Wooyung Rd/Tweed Valley Way Intersection during camping departures.

A reduced speed zone on Tweed Valley Way is proposed from approximately 540m south-east of Yelgun Road to 100m north of Jones Road. Free flow vehicle speeds on Tweed Valley Way are relatively high, in particular on the downhill section from Jones Road towards Gate B. Reducing the speed limit at the site frontage will improve safety with respect to traffic leaving the site as well as traffic queued in the right turn lane on Tweed Valley Way. This reduced speed zone is continued to Jones Road similarly as was done during previous festivals for service vehicles entering and exiting Jones Road.

A no stopping zone is proposed on Tweed Valley Way and Brunswick Valley Way from Shara Boulevarde in the south to the Byron Shire boundary in the north. The purpose of this is two-fold:

- Eliminate parking by patrons not familiar with the area on Tweed Valley Way which is a high speed road;
- Improve tools to manage trespassers, in particular from the north.

Chartered Professional Engineers and Scientists

Similar to recent Splendour in the Grass and Falls events at North Byron Parklands, patrons travelling along the Pacific Motorway will be encouraged to exit the Motorway at Pottsville and at Brunswick Heads to alleviate pressure on Yelgun Interchange. Experience with previous events has shown that this method is particularly effective for campers who are not as familiar with the local road network as local day patrons.

#### 2.3 Temporary Bus Bay Brunswick Heads

The Traffic Control Plan, includes a plan for Temporary Bus Bay Park Street, Brunswick Heads. The purpose of this plan is to provide a safer bus stop for the expected increase in bus patronage due to the Falls Festival.

It is proposed that the Park Street bus stop will also be utilised by the Falls Shuttle bus service. The implementation of the temporary bus bay plan includes:

- 1. Falls Festival intends to provide a security guard at this bus stop to ensure crowd control and to keep the footpath adjacent to the bus stop passable.
- 2. Falls Festival will also provide a clean-up team to service this area. This would ensure that the bus stop area remains clean and tidy so that the Brunswick Community and Council are not left with a clean-up problem as a result of the additional bus patronage due to the festival.
- 3. Water filled barriers, as per the Temporary Bus Bay Plan, are proposed to provide added safety for patrons. The need for these barriers is because the footpath at the location of the bus stop is raised and there is a garden bed, both of which reduce the available footpath space for persons waiting for buses.

This plan has been prepared to address a request from local shop keepers in Park Street that sought to have additional facilities for the increased bus patronage as a result of the similar festivals in the past.

#### 2.4 Stacked parking and camping

It is proposed to carry out stacked camping and parking at the Falls Festival Byron. This method has been tried and tested at the Falls & Splendour festivals in Byron. A schematic figure of this arrangement is depicted in Figure 2.

Chartered Professional Engineers and Scientists



Figure 2 - Stacked camping and parking

The process of stacked parking and camping is as follows.

As camper vehicles arrive, they are directed to a certain area, where they will be parked behind the car in front of them and parallel to vehicles besides them. The patrons then set up their tent next to their car. An aisle is kept free between two rows of tents for pedestrian and firefighting purposes.

After the patrons have parked their car, it will not be physically possible to leave the campgrounds in their own car before the car in front of them has done so. Thus, there will be no private car traffic generation by 2 and 3 day campers during event days. Private car traffic generation by campers resulted in significant traffic volumes during the festival days of a previous Falls Festival. This issue has thus been resolved.

Charter buses will be sourced by festival management to ensure sufficient transport capabilities are available during the festival, in particular for day trippers to Pottsville, Brunswick Heads and Byron Bay. We understand that in recent years, additional bus trips are scheduled for Brunswick Heads and less trips for Byron Bay to alleviate the congestion at Byron Bay and improve the economic benefits to local business in Brunswick Heads.

Internally, as the separation between car parking and camping has been removed (as is depicted in Figure 3), there is increased flexibility for directing traffic flows through the site. Any congestion due to ticketing issues or wet weather can thus be more easily negated.

It should be noted that this system of stacked parking and camping fundamentally differs from the combined parking and camping that caused the congestion during SITG 2013. During that festival, there was insufficient infrastructure in place to direct traffic flows and also the camping and parking was ad-hoc, not structured. The proposed structured parking/camping system for the coming Falls Festival at Byron has been tried and proven at the Falls festival in Lorne for years and also for recent Falls Festival Byron and Splendour in the Grass events.

Chartered Professional Engineers and Scientists

Festival management will liaise with the NSW Police to encourage drug searches to occur after vehicles have been parked in order to prevent any hold ups during peak arrival periods. Ticketing by mobile ticketing stations also occurs after vehicles have been parked.

Lastly, we have been informed that the stacked parking/camping system is likely to improve patron experience on the campers departure day. Patrons will better understand that they cannot leave the site until the vehicle in front of them has left, thus enhancing acceptance of delays.

In summary the benefits of the structured stacked parking/camping system are as follows:

- Elimination of private vehicle traffic generation by day trippers during the festival;
- More efficient use of space;
- Improved convenience for campers, having the tent set up next to their car;
- Improved patron experience during the departure day.




Figure 3 - Stacked parking/camping marked in blue

Chartered Professional Engineers and Scientists

#### 3.0 Traffic impact modelling

No traffic impact modelling has been undertaken for the 2020/21 event.

The upgrading of the Link Road intersection during 2016 has relieved the major bottleneck for traffic arriving at the festival site. Falls Festival events since the upgrade have resulted in no known traffic KPI breaches or traffic safety issues around the Link Road, and therefore no impacts on the Pacific Highway.

Observations during camping arrivals at the 17/18 Falls Festival resulted in some concerns regarding the peak arrival period impacts on TVW. With an additional day for camping arrivals, the existing intersection arrangements and TCPs are considered sufficient. In addition, there is a documented contingency TCP included.

If due to the traffic volumes the Spine Road would experience congestion, the following mitigation measures could be employed:

- Use southern car park for a snake or for temporary parking during a peak;
- Close southbound traffic on Spine Road and create a 2-lane one-way northbound situation during peak ingress using cones or bollards. Sufficient staff and material are to be present on site to instigate this if required.
- Direct outbound traffic to Gate E to separate inbound and outbound traffic streams if required.

Based on the previous modelling carried out for this event, the public road network has the capacity to cope with the traffic scenarios modelled for this event. The Spine Road would need to be monitored closely during the peak ingress period to be able to enact mitigation measures if the Spine Road reaches capacity.

### 4.0 Contingencies and emergency evacuation

North Byron Parklands has constructed roads within the site which are above various flood levels. North Byron Parklands has machinery, such as a large tractor, to tow vehicles which may have broken down on the internal road system. The Falls staff will be trained in the need to keep the internal roads clear, and if necessary arrange a contra flow situation, to temporarily pass a broken down vehicle.

Any contingency measures carried out by relevant authorities are to ensure the safety of any persons associated with the cause of the contingency measures to be carried out, as well as the efficient operation of the road network. It is paramount that queuing on the Pacific Motorway, Tweed Valley Way and Brunswick Valley Way be prevented at all times.

As the Police have the authority to take control of the site in an emergency, the Traffic Control Plan will then be overridden as the Police see fit.

As part of good management of the operation of this Traffic Control Plan, it is necessary that all relevant staffed be adequately briefed on the possibility of the need to evacuate the site in an emergency. In the case of bushfire and flooding there is some warning time that is available to the Police, to give them the opportunity to prepare to evacuate the site.

With the formalisation of Gate E, the site now has major entry and exit points both to the north and south. It will be necessary for the appointed traffic control staff to be on duty during an emergency evacuation, to quickly and efficiently move patrons through the site to the exit points.

Chartered Professional Engineers and Scientists

The evacuation strategy by the Police is to take into account time of day, site occupancy and suitability of access roads. If the site is full and the call for evacuation is made by the Police, orderly egress commencing with the day patrons, followed by the campers, will be necessary.

The draft emergency evacuation plan for fire, nominates that patrons congregate in "assembly points" and from there the whole site would then be evacuated. This would be at the discretion of the LEMO Police Controller.

The draft emergency evacuation plan for the fire addresses different evacuation scenarios. In instances where evacuation by vehicle is available, evacuation is to the various entry/exit points. In instances where vehicle evacuation of the site is not appropriate, emergency assembly locations within and adjoining the site are nominated for site occupants to assemble under supervision.

Emergency vehicle access is available from Gate C, Gate D, Jones Road (Gate A) and Wooyung Road (Gate E).

Although no traffic controllers are required to manage traffic under normal conditions, traffic controllers would need to be on call to assist in managing queues during any queuing on the public road that may occur as a result of unforeseen circumstances. Back of queue warning vehicles would need to be available to warn inbound vehicles on the public road of any queues ahead. It is the responsibility of the festival management to ensure the public road is monitored and potential queuing is predicted in advance of any queuing appearing.

### 5.0 Monitoring for Traffic Management During the Festival

Traffic monitoring is required to provide input for the Performance Evaluation Report under the current approval for the site.

It is proposed to install classified traffic counters at the locations listed below, at least two weeks before the Festival. These counters will be used to gain a confirmation of the background traffic levels, and then the increase that can be attributed to the Festival.

- North bound off ramp at Yelgun;
- South bound off ramp at Yelgun;
- North bound on ramp at Yelgun;
- South bound on ramp at Yelgun;
- Tweed Valley Way to the North of Jones Road;
- Tweed Valley Way between Yelgun Road and Billinudgel Road;
- Brunswick Valley Way opposite the Yelgun Rest Area;
- Spine Road (2 counters each lane);
- Wooyung Rd east of Gate E;
- Wooyung Rd West of Gate E.

On-site surveys will need to be carried out to estimate the vehicle occupancy for camper vehicles. Data on the use of any bus services is to be provided by Festival Management after the event so that mode-share calculations can be carried out.

Chartered Professional Engineers and Scientists

#### 6.0 Risk assessment

A risk assessment for the traffic operation of this festival is described in this chapter. The risk assessment is set up such to identify potential risks to public health as a result of the festival traffic operations. The key performance indicators (KPI's) as defined by the development approval are aimed to reduce the likelihood of occurrence by requiring management of traffic queue growth and level of service.

Additional risk reducing measures such as contingency plans and creating a temporary low speed environment at high risk locations are part of the traffic management tools recommended in this Traffic Management Plan.

Lastly, there are risks due to hazards that might occur that are outside the control of the event management or traffic controllers. These hazards would include extreme weather conditions and crashes on the public road due to drivers' negligence. In order to reduce the risk effect of these hazards, risk mitigating strategies are recommended in this risk assessment.

It is noted that it is the combined responsibility of festival management and government authorities to ensure that there is sufficient funding available and personnel in place for adequate implementation of the traffic control plans, infrastructure and risk mitigation measures.

The risk assessment proposed in this report is provided as a guide. We recommend that after all relevant staff, consultants and contractors have been engaged, that a risk management meeting is held prior to the event. During this risk management meeting a final risk assessment shall be established which would be included in the event management manual. This risk management meeting shall include:

- NBP General Manager
- Falls Byron General Manager
- · Event Traffic Manager
- Traffic Engineer
- Traffic Control Manager
- Police representative
- Ambulance representative
- RFS representative
- RMS representative
- Council representatives (BSC and TSC)

The classification of risks for the purpose of this risk assessment is depicted in Figure 4 and associated definitions are provided in Table 2.

Chartered Professional Engineers and Scientists

Figure 4 - Risk classification matrix

		LIKELYHOOD OF OCCURANCE					
		Very likely (could happen anytime)	2. Likely (could happen sometime)	3. Unlikely (could happen, but only rarely)	4. Very Unlikely (could happen but probably never will		
	A. Death or permanent disability	1	1	2	3		
CONSEQUENCE	B. Long term illness or serious injury	1	2	3	4		
CONSEC	C. Medical attention or several days off work	2	3	4	5		
	D. First aid needed	3	4	5	6		

Table 2 - Risk definitions

Risk Class	Time Frame for Corrective Action	Role/Responsibility
Class 1 – Extreme risk	Immediate action required	Senior management –
		Executive
Class 2 – Very high risk	Immediate action required	Senior management
Class 3 – High risk	Immediate action required	Senior management
Class 4 – Medium risk	Close-of-business of current	Management responsibility
	day	must be specified
Class 5 – Low risk	Within 24 hours	Manage by routine procedures
Class 6 – Very low risk	Within 48 hours	Manage by routine procedures

The risk assessment is provided below.



Chartered Professional Engineers and Scientists

	•	Γ		T	R	ISK ASSESSME	NT	•	ı			
				In	itial Risl	c Rating		Person responsible for Responsible person ensuring sufficient		Residual Risk Rating		Rating
Activity	Hazard description	Direct consequence	Potential indirect consequence	L	С	Risk Class	Method for risk mitigation	formitigation implementation	funding to enact mitigation	L	С	Risk Cla
Traffic control on public road	Traffic controller hit by car	Injury or death	Traffic congestion and queue growth	3	А	2	Ensure proper implementation of traffic control plan Ensure TC staff compliance with WHS regulations and other relevant	Traffic control manager Supervisors and	Festival General Manager Festival General	4	А	3
On-site vehicle processing	Insufficient rate at which vehicles are processed	Traffic congestion and queue growth	Collision on public road	2	А	1	legislation  Ensure sufficient staff for vehicle processing Ensure adequate equipment to enable staff to process vehicles safely and efficiently Enactment of snake in southern car park to create additional vehicle storage Traffic controllers on public road to control back of queue	Parking manager  Parking manager  Event traffic manager  Traffic control manager	Festival General Manager	4	А	3
	Higher patron arrival flow than anticipated	Traffic congestion	Collision on public road	2	А	1	Traffic management plan to allow for sufficient contingency Contingency plans available for enactment if needed Queue warning vehicle implementation	Traffic Engineer Traffic Engineer and traffic control manager Traffic control manager	Festival General Manager Festival General Manager Festival General Manager	4	А	3
	More concentrated arrival peak than anticipated	Traffic congestion	Collision on public road	2	А	1	Traffic management plan to allow for sufficient contingency Contingency plans available for enactment if needed Queue warning vehicle implementation	Traffic Engineer Traffic Engineer and traffic control manager Traffic control manager	Festival General Manager Festival General Manager Festival General Manager	4	А	3
Patron arrival, departure and additional festival traffic generation throughout event	Crash on critical intersection or traffic lane	Injury or death	Traffic congestion and queue growth	3	А	2	Provide required aid to persons involved Manage traffic at crash site  Manage back of queue	Police Emergency services Police Traffic control manager	NSW Police Force NSW Ambulance Service NSW Police Force Festival General Manager	4	А	3
	On-site crash	Injury or death	Traffic congestion and queue growth	2	А	1	Ensure adequate on-site road network  Ensure sufficient visibility through corners  Ensure low speed environment Prevent occurrence of sudden stopping Secure crash site Provide required aid to persons involved Manage traffic at crash site  Manage back of queue	NBP General Manager NBP General Manager and Event Traffic Manager  Event traffic manager  Event traffic manager Police  Emergency services Police  Traffic control manager	NBP shareholders NBP shareholders and Festival General Manager Festival General Manager Festival General Manager NSW Police Force NSW Ambulance Service NSW Police Force Festival General Manager	3	С	4
	On-site vehicle break down	Traffic congestion and queue growth	Collision on public road	2	А	1	Remove vehicle from traffic lane Enactment of snake in southern car park to create additional vehicle storage Traffic Management Plan to include low speed zones in high risk areas Traffic controllers on public road to control back of queue	Event traffic manager  Event traffic manager  Traffic Engineer  Traffic control manager	Festival General Manager  Festival General Manager Festival General Manager Festival General Manager Manager	4	В	4
	Queue on motorway, motorway off ramp or arterial road	Traffic congestion and queue growth	Potential back of queue crash	3	А	2	Contingency plans available for enactment if needed Queue warning vehicle implementation	Traffic Engineer and traffic control manager Traffic control manager	Festival General Manager Festival General Manager	4	А	3
	On-site fire or bush fire	Panic by drivers	Potential collisions on site and public road	2	А	1	Fire prevention by site planning, vegetation maintenance and crowd control Fire identification and fighting	NBP General Manager and Event Manager RFS and Event manager	NBP shareholders and Festival General Manager RFS and Festival General Manager	. 2	D	4
	Severe wind, rain and/or hail	Sudden stop of traffic flow and uncontrolled placing of vehicles on traffic lane and road shoulder	Collision	2	А	1	Monitor weather and issue sever weather warnings to staff, contractors and patrons Queue warning vehicle implementation VMS text to be changed to warn drivers of severe weather and traffic congestion	Event manager Traffic control manager Traffic control manager	Festival General Manager Festival General Manager Festival General Manager	3	В	3



Chartered Professional Engineers and Scientists

## 7.0 Copies of the Traffic Management Plan

Copies of the Traffic Management Plan, after signature by the relevant persons nominated in the plan, shall be forwarded to the following authorities as a reference should there be any need for contact, such as in the case of an emergency.

- NSW Police Force,
- The local RMS office at Grafton,
- The NSW Ambulance Service,
- The Rural Fire Service, and
- Byron Shire Council.

#### 8.0 Audit checklist

Any Traffic Controllers shall complete the TCP Audit Check list as included in this report, before the start of the Festival and immediately prior to the closure of the Festival. The aim of this audit is to ensure that all the requirements of the TCP have been in place for the full duration of the event.

Chartered Professional Engineers and Scientists

AUDIT	CHECKLIST						
Date:	Time:	Auditor:					
Office	/Company:	Site Super	rvisor:				
Locati	on:						
Nature of Activity:							
Duration of Activity:							
Road Configuration:							
1	Provision for Activity	YES	NO	N/A			
1.1	Has an approved TCP been provided						
2	Implementation						
2.1	Are all signs & devices installed in accordance						
	with TCP?						
2.2	Are there any contradictory, distracting or						
	superfluous signs or markings?						
2.3	Are signs suitably placed with regard to:						
2.3.1	Sight distance						
2.3.2	Motorists approaching at high speed						
2.3.3	Queue lengths						
2.3.4	Visibility, shade, light glare?						
2.4	Are all signs displayed appropriate for the						
	current conditions?						
2.5	Are there any damaged or defective signs?						
2.6	Have the needs of pedestrians been						
	considered?						
2.7	Have the needs of cyclists been considered?						
2.8	Are safety barriers required?						
2.9	Are safety barriers installed correctly?						
2.10	Has access to the site been provided?						
3	Documentation Sighted						
3.1	TCP, including details & modifications						
3.2	Direction to Restrict (DTR)						
3.3	Traffic controllers certification						
4	Has the Signage been covered for non RTA						
	Controllers operation as specified on the TC						
C = 1111	Plan						
Comm	nents/Findings						
Recon	nmendations/Corrective Action						
Audito	r (signed)	Site Superv	visor:				

Chartered Professional Engineers and Scientists

## 9.0 Responsible organisations contact persons and signatures

The following persons have read and understand this Traffic Management Plan prepared for The Falls Festival 2020/2021, to be conducted at the North Byron Parklands, Tweed Valley Way, Yelgun, and will implement this plan.

Senior Accredited Traffic Controller: Name of responsible person who can be contacted on t	he following phone numbers:
Name:	Signature:
Phone:	Mobile Phone:
Festival Site Manager: Name of responsible person who can be contacted on t	he following phone numbers:
Name:	Signature:
Phone:	Mobile Phone:

### 10.0 Approval condition compliance summary table

This TMP has been prepared in accordance with the RMS Guide to Traffic and Transport Management for Special Events. **Table 3** below summarizes the compliance with the conditions of approval as listed in chapter 1.

Table 3 - Condition compliance summary table

Condition	Compliance	Location
	achieved (y/n)	
B4 – Traffic management and parking	У	Chapter 2 and 3
C9 – Transport Management Plan	у	Chapters 2 and 3
C10 – Traffic Control Plans	у	Appendix B and C
C45 – Car Parking Management	у	Chapter 2
C46 – Access for Emergency Vehicles	у	Chapter 8
C47 – Pedestrian Access from Day Parking Area	У	Appendix A
C48 – Disabled Access	у	Appendix A
C51 – Emergency Evacuation plans	у	Chapter 8

#### 11.0 Chain of command

The Traffic Engineer (TE) will be present at the site or the surrounding road network generally at the times of peak event traffic activity undertaking traffic monitoring and observations.

The responsibilities of the TE are:

- Certification of the installation and proper implementation of TMP and TCP,
- Liaison with Falls Festival management and Site Manager,
- Liaison with Traffic Control Supervisor,
- Undertake Traffic Monitoring activities,
- Provide Traffic Evaluation Report following each event.
- Design and Modification of existing approved Traffic Control Plans when required,
- Certification of new Traffic Control Plans when required.

The Traffic Control Manager (TCM) will be present at the site or surrounding road network during peak arrival and departure periods, and be available at all times to implement contingency measures.

The responsibilities of the TCM include:

- Liaison with Falls Festival management and Site Manager,
- Liaison with Camping Manager,
- · Liaison with Parking Manager,
- Liason with Traffic Engineer,
- Liaison with Council and RMS,
- Liaison with NSW Police,

Changes to Traffic Control Plans can only be made by an RMS accredited person with a Prepare a Work Zone Traffic Management Plan card. This would normally be either the TE or the TCM

Chartered Professional Engineers and Scientists

The TCM will supervise the operation of the TMP and TCP and ensure that the Traffic Controllers are advised of their roles in the traffic management. The TE will report any significant issues observed to the TCM as required.

The Event Management would be expected to contact the TE or TCM to discuss any traffic matters. The success of the implementation this TMP depends on a coordinated managed traffic approach and this will be achieved by following a chain of command protocol. This will also be reinforced in the Protocol issued to the contracted traffic control company.

#### 12.0 Conclusions and recommendations

With demand management and close supervision of the traffic and parking it is possible to manage the 2020/21 Falls Festival at Yelgun such that it does not adversely impact on the Pacific Motorway or the local road network, outside the levels nominated in the development consent.

The KPI's nominated in the project approval can be met when the festival is managed as per this TMP.

An appropriately qualified traffic engineer should be present at critical times to enable effective evaluation of the implementation of the TMP and traffic control plans and make adjustments where required.

A designated person from Festival Management should also be the point of contact, with respect to traffic, camping patrons entry and day parking issues, buses and taxis, and for the liaison between traffic controllers, parking attendants and camping operators, RMS, Police, Byron Shire Council and Festival Management.

Traffic counters will be installed to monitor traffic flows both for rate and volume. Monitoring of the operation of the car parks, in particular the operation of the car parks for ingress and egress, is to be performed to ensure effective operation of the car parks.

Chartered Professional Engineers and Scientists

## **APPENDIX A – Traffic control plans**